



1 FLOOR PLAN - TELCOM
T3.00 SCALE: 1/4" = 1'-0"

GENERAL NOTES:

- A. FOR VOICE/DATA OUTLETS PROVIDE "RANDL 5X5" BOXES WITH A 1.25" PURPLE CONDUIT TO ACCESSIBLE CEILING SPACE. TERMINATE CONDUIT WITH END CONNECTORS AND THREAD ON PLASTIC BUSHING FOR CABLE PROTECTION. OUTLET SHALL BE AT THE SAME HEIGHT AS ADJACENT POWER OUTLET AND LESS THAN 18" SEPARATION. COORDINATE WITH ELECTRICAL.
- B. COORDINATE ALL DEVICE LOCATIONS WITH LATEST ARCHITECTURAL INTERIOR ELEVATIONS TO VERIFY DEVICES WILL NOT BE OBSTRUCTED.
- C. PROVIDE PULL STRING IN ALL CONDUITS FOR LATER USE.

NOTES:

- 1. PROVIDE "RANDL 5X5" BOXES WITH A 1.25" PURPLE CONDUIT TO ACCESSIBLE CEILING SPACE PER BOX INDICATED.
- 2. COMBO FURNITURE FLOOR BOX. PROVIDE WITH ALL NECESSARY HARDWARE, COMPARTMENT DIVIDERS, AND FINISH FLANGE FOR A COMPLETE INSTALLATION. PROVIDE COVERPLATES WITH 1" SCREW PLUG AND 2" SCREW PLUG. VERIFY COVERPLATE FINISH WITH ARCHITECT. COORDINATE EXACT LOCATION WITH FURNITURE VENDOR AND ARCHITECT PRIOR TO ROUGH-IN. LEGRAND "EFBFF-06" SERIES. PROVIDE (2) 1" CONDUITS TO ACCESSIBLE CEILING SPACE.
- 3. FLOOR BOXES SPECIFIED AND LOCATED PER ELECTRICAL, PROVIDE (2) 1" CONDUITS TO ACCESSIBLE CEILING SPACE FOR LOW VOLTAGE CABLING.

FIRE ALARM AND DETECTION SYSTEM SHOWN ON PLAN(S) ARE FOR DESIGN INTENT ONLY. THIS IS A DEFERRED SUBMITTAL SYSTEM REQUIRING THE CONTRACTOR TO COMPLETE THE PERMIT READY DESIGN AND CALCULATIONS AS REQUIRED PER THE AUTHORITY HAVING JURISDICTION. VERIFY BUILDING OCCUPANCY TYPE AND OCCUPANT LOAD WITH ARCHITECTURAL PLANS.

MFA INC.
Consulting Engineers
2007 S.E. Ash St.
Portland, OR 97214
PHN: (503) 234-0548
FAX: (503) 234-0677
WWW.MFA-ENG.COM
CONTACT: GARY ADOVNIK



South Hillsboro Crossing Clinic
OHSU Tuality Health care
7529 SE Tuatatin Valley Hwy., Hillsboro, Oregon 97123



ISSUE DATE: 12.19.18
REVISIONS:

FLOOR PLAN - TELCOM

T3.00

PERMIT SET